SPECIFICATIONS		A
BETWEEN FRAME RAILS	6" TO 54"	1
ROLL CONSTRUCTION	STRUCTURAL ROUND TUBE, 1.9" DIAMETER, 0.145" WALL STEEL	3
BEARING TYPE	SEMI-PRECISION, CARBON STEEL HOUSING, GREASED, 7/16" HEX	7 4
AXLE RETENTION	STANDARD - SPRING LOADED ONE SIDE. OPTIONAL: COTTER PIN OR FIXED AXLE	
ROLLER SURFACE	STANDARD CARBON STEEL	
STANDARD SPROCKETS	50A18	
MINIMUM C-C	5"	
		_

AVAILABLE OPTIONAL FEATURES:

- . CUSTOM AXLE EXTENSION FROM BFR
- 2. CUSTOM SPROCKETS SPACING
- 3. NON STANDARD SPROCKETS
- . PVC COVER

